

ADDENDUM #1

FLBS SOUTH SEWER LIFT STATION FLATHEAD LAKE BIOLOGICAL STATION POLSON, MONTANA A/E #2016-01-01-01

January 18, 2018

To Prospective Bidders,

The provisions of this Addendum #1 shall apply to and be a part of the Contract Documents. This Addendum consists of 2 pages including the following changes:

SPECIFICATIONS

1. Bid Item 112 in the Bid Form and SECTION 01270 MEASURE AND PAYMENT will allow Schedule 40 PVC pipe as an alternate. The service line does not have to be HDPE, but it shall have a 4.500" OD (outside diameter) in order to create a water tight seal with the grommet provided by E-One. Schedule 40 PVC will be an acceptable alternative contingent upon meeting the requirements of the manufacturer's installation instructions.
2. Bid Item 106 and 108 in SECTION 01270 MEASURE AND PAYMENT and SECTION 02620 HIGH DENSITY POLYETHYLENE (HDPE) PIPE AND FITTINGS states that the 1.25" HDPE pipe shall be de-beaded. Do to the difficult nature in de-beading a 1.25" pipe, it will be acceptable to butt fuse the 1.25" HDPE pipe **without** de-beading.
3. Liquidated damages: As stated on page 1 (one) of the STANDARD FORM OF CONTRACT BETWEEN OWNER AND CONTRACTOR FOR CONSTRUCTION, "If the Work is not completed within the time specified, the Owner may assess liquidated damages in the amount of: **FIVE HUNDRED AND NO/100 DOLLARS (\$500)** PER CALENDAR DAY".

On page 33 of the GENERAL CONDITIONS the liquidated damages reads, "The Contractor and his surety shall be liable for and shall pay to the Owner the sums hereinafter stipulated as liquidated damages for each calendar day of delay until the work is substantially complete: **ONE HUNDRED AND NO/100 DOLLARS (\$100.00)**".

Page 33 is incorrect and shall be changed to read, "**FIVE HUNDRED AND NO/100 DOLLARS (\$500)**".

CONSTRUCTION DRAWINGS

1. The following changes shall be made to the Construction Drawings.

Sheet 4: The new service line from the Director's House to the new Grinder Pump Station note reads, "48 LF OF NEW 4" DR15.5 HDPE SERVICE LINE INSTALLED AT 2% SLOPE". The note shall read, "48 LF OF NEW 4" SERVICE LINE WITH A 4.500" OD INSTALLED AT 2% SLOPE".

Sheet 5: The note to remove the existing lift station in detail 4/5 reads, “REMOVE EXISTING LIFT STATION 1 FOOT BELOW GRADE AND FILL WITH GRAVEL, 6” OF TOPSOIL ON SURFACE AND SEED”. The note shall read, “REMOVE EXISTING LIFT STATION 2 FEET BELOW GRADE AND FILL WITH GRAVEL, 6” OF TOPSOIL ON SURFACE AND SEED”.

GENERAL

1. The electric service for the existing lift station along the beach will be disconnected by Mission Valley Power, at the request of the OWNER. Mission Valley Power asked for a minimum of 2 days lead time before demolition of the lift station is to take place.
2. Contractors remember to acknowledge this Addendum #1 on cover of Bid Proposal Envelopes and on the BID PROPOSAL, as noted in Instructions to Bidders.
3. **To bid this Project, Bidders must submit a bid on the 25th of January by 2:00 pm as described in the Instructions to Bidders.**

END OF ADDENDUM No. 1

Scott Anderson, P.E. #7978 MT

